Verkehrsmonitoring Zürich West, Faktenblatt


Messstellen-ID Z102 Knoten Nr. 454

Ort Badenerstrasse (Farbhof)


Typ DAV
Richtung 1 (R1) auswärts
Richtung 2 (R2) einwärts

Zeitraum Von 2024-02-05 bis 2024-02-18

Bauphase 0



Kennwerte		R1	R2	QS
alle Tage				
DTV	[Fz/d]	5'152	6'919	0
DTV-16 6-22 Uhr	[Fz/16h]	5'041	6'760	11'801
DTV-8 22-6 Uhr	[Fz/8h]	471	642	1'113
Werktage (Mo-Fr)				
DWV	[Fz/d]	5'762	7'761	13'523
DWV-16 6-22 Uhr	[Fz/16h]	5'041	6'760	11'801
DWV-8 22-6 Uhr	[Fz/8h]	471	642	1'113
MSP 7-8 Uhr	[Fz/h]	287	547	834
ASP 17-18 Uhr	[Fz/h]	437	545	982




Wochenganglin	ie	R1	R2	QS
Montag	[Fz/d]	5'601	7'457	13'058
Dienstag	[Fz/d]	5'668	7'676	13'344
Mittwoch	[Fz/d]	5'765	7'750	13'515
Donnerstag	[Fz/d]	5'737	7'753	13'490
Freitag	[Fz/d]	6'041	8'170	14'211
Samstag	[Fz/d]	5'383	7'113	12'496
Sonntag	[Fz/d]	1'870	2'514	4'384




Entwicklung DWV über Zeit











Kommentare/Beobachtungen